MYSORE DIVISION.

ADVERTISEMENT.

The 12th November 1889.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 3rd December 1889, for constructing a new Taluk Cutcherry at Heggaddevankote. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1891.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Items of Work.	Per.	Rate.	Quantity.
Prisoners dock and witness box	L. S.		Rs.
Earthwork excavation	C. Yd.		459
Earthwork filling, earth from excavation to be utilized	,,		320
Rough stone in mortar	C. Ft.		11,010
Brick in mortar	,,		23,278
Do arch work	,,		498
Slab stones	S. Ft.		2,683
Concrete flooring	C. Ft.		1,567
Doors, teak wood, complete	S. Ft.		484
Windows do	,,		281
Do glazed top do	,,		72
Do pannelled and iron bar 3″ a part	,,		120
Treasury room door	,,		23
Ventilators with iron bar	,,		59
Base stones for pilasters in front verandah	Each.		6
Stones roughly dressed for wooden brackets to rest on	,,		92
Plain cornice work	R. Ft.		220
Cornice work	,,		146
Teak wood work	C. Ft.		686
Roofing with teak reepers and 1st class Mangalore tiles	Sqr.		110·96
Pakka terrace	,,		1·56
Plastering with chunam	,,		303·12
Teak wood ornamental eave boards 8″	R. Ft.		399
Do 12″ deep and ¾″ thick	,,		332
Fenials	Each.		7
White and color washing	Sqr.		303·12
Teak wood planked ceiling ¾ thick	,,		11·05
Zinc guttering to valleys	R. Ft.		106
Pointing	Sqr.		14·14
Wood oiling	,,		87·78
Bamboo matting with outer rind	,,		26·86
Record racks	L. S.		Rs.
Whiteant composition	Sqr.		19·29
Masonry drains	Each.		2
Compound trench and gate with drains, &c., complete	L. S.		..
Clearing site	,,		..
Iron work for trusses	,,		..

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing a new Taluk Cutcherry at Heggaddevankote"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8 On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

V. H. KARVE, L. C. E.,
Executive Engineer.